


POST MILES SHEET TOTAL TOTAL PROJECT NO. SHEET

Delis

C51434

EXP. 6-30-08



ű

œ

- 1/4" Bevel

NOTE:

(1) Make smooth cuts from the bottom of seal to $1\frac{1}{2}$ " clear of top leaving at least one complete cell between the top of the cut and top of the seal. When necessary cut back of seal to clear conduit and round openings.

REGISTERED CIVIL ENGINEER

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this p

To accompany plans dated .

The Contractor shall verify all controlling field

dimensions before ordering or fabricating any

October 5, 2007

PLANS APPROVAL DATE

- ② Opening in barrier to match width of sawn deck joint.
- $\ensuremath{\mathfrak{F}}$ Sawcut groove widths shall be as ordered by the Engineer.
- 4 Depth of sawcut: Type A Depth to be 2" minimum. Type B - Depth to be equal to or greater than the depth of seal measured along the contact surface, when compressed to minimum width position (W2) plus dimensions shown.
- MR (movement rating) as shown on other plan sheets.
- Other depths must be approved by the Engineer.

DIMENSIONS "a" OF JOINT REQUIRED

| Movement Rating | | "a" Dimension | | | | |
|-----------------|----------------------|----------------------|-----------------|--------|--|--|
| (MR) | Bridge | Deck Concrete Placed | | | | |
| 5 | Туре | Winter | Fall- Spring | Summer | | |
| 2" | All except CIP/PS | 11/2" | 11/4" | ₹4" | | |
| _ | CIP/PS | 11/4" | 1" | 1/2" | | |
| 11/2" | All except CIP/PS | 11/4" | 1" | 1/2" | | |
| 172 | CIP/PS | 1" | 3/4" | 1/2" | | |
| 1" | All except CIP/PS | 1" | 3/4" | 1/2" | | |
| ' | CIP/PS | 3/4" | 1/2" | 1/2" | | |
| 1/2" | All except CIP/PS | 3/4" | 3/4" | 1/2" | | |
| /2 | CIP/PS | 1/2" | 1/2" | 1/2" | | |


STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

JOINT SEALS (MAXIMUM MOVEMENT RATING = 2")

NO SCALE

RSP B6-21 DATED OCTOBER 5, 2007 SUPERSEDES STANDARD PLAN B6-21 DATED MAY 1, 2006 - PAGE 258 OF THE STANDARD PLANS BOOK DATED MAY 2006.





Maximum

6'-0"

8'-0"

10'-0"

12'-0"


14'-0"


16'-0"

C47240

CIVIL

Exp. 12-31-07





SPREAD FOOTING SECTION

a)bars @

#4

#4

#5

#6

#6

6'-0"

8'-0"

10'-0"

12'-0"

14'-0'

16'-0"

. '-4" Max

(b)bars @

#4

#4

#4

TYPICAL SECTION

⊕ Full mortar bed at bottom of wall

9

TRENCH FOOTING

| TIVEINGH FOOTING | | | | | | | |
|------------------|---------------|---------------|---------------|---------------|---------------|---------|--|
| | | CASE | 1 | CAS | E 2 | | |
| Maximum | Ø = 25 Min | Ø = 30 Min | Ø = 35 Min | Ø = 30 Min | Ø = 35 Min | Maximum | |
| " | D | D | D | D | D | - I | |
| 6'-0" | 5′-0" | 4'-3" | 3'-6" | 6'-6" | 5'-0" | 6'-0" | |
| 8'-0" | 6'-0" | 5'-0" | 4'-3" | 7'-9" | 6'-0" | 8'-0" | |
| 10'-0" | 6'-9" | 5′-9" | 5′-0" | 8'-9" | 6'-9" | 10'-0" | |
| 12'-0" | 7'-9" | 6′-6" | 5′-6" | 9'-9" | 7'-9" | 12'-0" | |
| 14'-0" | 8'-6" | 7′-3" | 6'-0" | 10'-9" | 8'-6" | 14'-0" | |
| 16'-0" | 9'-3" | 7'-9" | 6'-6" | 11'-9" | 9'-3" | 16'-0" | |

- Case 1 Level ground ($\pm 10\%$) on both sides of the sound wall.
- Case 2 Level ground ($\pm 10\%$) on traffic side of the sound wall and sloping ground on opposite side.

sides of the sound wall.

SPREAD FOOTING

| Maximum H | w |
|--------------|-------|
| 6'-0" | 3'-0" |
| 8'-0" | 4'-0" |
| 10'-0" | 5′-0" |
| 12'-0" | 5'-9" |
| 14'-0" | 6'-6" |
| 16'-0" | 7′-6" |

A. For type of block and joint finish, see other sheets.

SOUND WALL REINFORCEMENT TABLE

6'-0'

8'-0'

10'-0"

GENERAL NOTES:

(psi)

1500

1500

1500

1500

1500

2000

- B. When blocks are laid in stacked bond, ladder type, galvanized joint reinforcement shall be provided. A minimum of 2-9 gauge wires continuous at 4'-0" maximum to be used. Locate reinforcement in joints that are at the approximate midpoint between bond and beams.
- C. Horizontal joints shall be tooled concave or may be weathered. Vertical joints shall be tooled concave or may be raked.

REGISTERED CIVIL ENGINEER

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this pla

October 5, 2007

PLANS APPROVAL DATE


- D. For intermediate wall heights that are between the "H's" given, use the tabular information for the next higher "H".
- E. Masonry strengths are listed in the "SOUND WALL REINFORCEMENT TABLE".

SOUND WALL MASONRY BLOCK ON FOOTING **DETAILS (1)**

NO SCALE

RSP B15-1 DATED OCTOBER 5, 2007 SUPERSEDES STANDARD PLAN B15-1 DATED MAY 1, 2006 - PAGE 291 OF THE STANDARD PLANS BOOK DATED MAY 2006

REVISED STANDARD PLAN RSP



TRENCH FOOTING SECTION

For details not shown, see Case 1. Level ground (±10%) on one side of the sound wall and sloping ground

on the opposite side.

For details not shown, see Case 2. Level ground (±10%) on both sides of the sound wall.

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

Compressive

Strength of CMU

(psi)

1900

1900

1900

1900

1900

2800

| | Douglas / Junes REGISTERED CIVIL ENGINEER |
|-------------------------------------|--|
| RAL NOTES: | October 5, 2007 PLANS APPROVAL DATE October 5, 2007 PLANS APPROVAL DATE October 5, 2007 PLANS APPROVAL DATE |
| and joint finish, see other sheets. | The State of California or its officers or agents stall not be responsible for the accuracy or completeness of electronic copies of this plan sheet. |
| nid in stacked bond ladder type | • |

To accompany plans dated.

DIST COUNTY

GENE

- A. For type of block
- B. When blocks are laid When blocks are laid in stacked bond, ladder type, galvanized joint reinforcement shall be provided. A minimum of 2-9 gauge wires continuous at 4'-0" maximum to be used. Locate reinforcement in joints that are at the approximate midpoint between bond beams.
- C. Horizontal joints shall be tooled concave or may be weathered. Vertical joints shall be tooled concave or may be raked.
- D. For intermediate wall heights that are between the "H's" given, use the tabular information for the next higher "H".
- E. Masonry strengths are listed in the "SOUND WALL REINFORCEMENT TABLE". See Standard Plan B15-3.

DESIGN NOTES:

DESIGN

f'c = 3.6 ksi

fy = 60 ksi

Uniform Building Code, 1997 Edition and the Bridge Design Specifications.

DESIGN WIND LOAD

DESIGN SEISMIC LOAD

0.57 Dead load 20 psf

REINFORCED CONCRETE


CONCRETE MASONRY

REGULAR STRENGTH

HIGH STRENGTH f'm = 2000 psi

f'm = 1500 psifb = 495 psi fs = 24,000 psi n = 25.8


f'm = 2500 psi fb = 660 psi fb = 830 psi fs = 24,000 psi fs = 24,000 psi n = 19.3



SECTION A-A

For details not shown, see other sections.

H=6'-0" THRU H=10'-0"



For details not shown, see other sections.


H=12'-0" THRU H=16'-0"

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

SOUND WALL MASONRY BLOCK ON PILE CAP DETAILS (2)

NO SCALE

RSP B15-4 DATED OCTOBER 5, 2007 SUPERSEDES STANDARD PLAN B15-4 DATED MAY 1, 2006 - PAGE 294 OF THE STANDARD PLANS BOOK DATED MAY 2006



- Lapped splices in spiral reinforcement shall be lapped at least 80 wire diameters. Spiral reinforcement at splices and at ends shall be terminated with a 135° hook with a 6" tail hooked around a longitudinal bar.

| | CASE 1 - PILE DATA TABLE | | | | | | | | | |
|--------------|--------------------------|--------|---------------|--------|--------|---------------|--------|--------|---------------|--------------|
| | | ø = 25 | Min | | ø = 30 | Min | | ø = 35 | Min | |
| Maximum H | S | L | Pile Reinf | S | L | Pile Reinf | s | L | Pile Reinf | Maximum H |
| 6'-0" | 16'-0" | 7'-0" | #6 To+ 6 | 16'-0" | 5′-6" | #6 To+ 6 | 16'-0" | 4'-6" | #6 To+ 6 | 6'-0" |
| 8'-0" | 16'-0" | 8'-6" | #6 To+ 7 | 16'-0" | 7'-0" | #6 Tot 7 | 16'-0" | 5'-6" | #6 To+ 7 | 8'-0" |
| 10'-0" | 16'-0" | 10'-0" | #7 Tot 6 | 16'-0" | 8'-0" | #7 Tot 6 | 16'-0" | 6'-6" | #7 Tot 6 | 10'-0" |
| 12'-0" | 15'-0" | 11'-6" | #8 To+ 7 | 16'-0" | 9'-6" | #8 To+ 7 | 16'-0" | 7′-6" | #8 To+ 7 | 12'-0" |
| 14'-0" | 13'-0" | 11'-6" | #8 To+ 7 | 14'-0" | 10'-0" | #8 To+ 7 | 14'-0" | 8'-0" | #8 To† 7 | 14'-0" |
| 16'-0" | 12'-0" | 12'-0" | #8 To+ 7 | 13′-0" | 10'-6" | #8 To+ 7 | 13'-0" | 8'-6" | #8 Tot 7 | 16'-0" |

- CIDH Pile

DETAIL D

* @ 2" at option of Contractor

.95

Case 1 - Level ground ($\pm 10\%$) on both sides of the sound wall.

| | CASE 2 - PILE DATA TABLE | | | | | | | | |
|--------------|--------------------------|----------|---------------|--------|--------|---------------|--------------|--|--|
| | | ø = 30 I | Min | | ø = 35 | Min | | | |
| Maximum H | S | L | Pile Reinf | S | L | Pile Reinf | Maximum H | | |
| 6'-0" | 16'-0" | 11'-6" | #8 Tot 7 | 16'-0" | 8'-6" | #6 To+ 7 | 6'-0" | | |
| 8'-0" | 16'-0" | 14'-0" | #8 To† 7 | 16'-0" | 10'-6" | #7 Tot 6 | 8'-0" | | |
| 10'-0" | 15'-0" | 16'-0" | #8 To† 7 | 16'-0" | 12'-0" | #7 Tot 7 | 10'-0" | | |
| 12'-0" | 12'-0" | 16'-0" | #8 To+ 7 | 15'-0" | 13'-6" | #8 To+ 7 | 12'-0" | | |
| 14'-0" | 10'-0" | 16'-0" | #8 To† 7 | 12'-0" | 13'-6" | #8 Tot 7 | 14'-0" | | |
| 16'-0" | 8'-0" | 16'-0" | #8 To+ 7 | 11′-0" | 14'-0" | #8 To+ 7 | 16'-0" | | |

Case 2 - Level ground (±10%) on traffic side of the sound wall and sloping ground on opposite side.

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

SOUND WALL MASONRY BLOCK ON PILE CAP DETAILS (3)

NO SCALE


RSP B15-5 DATED OCTOBER 5, 2007 SUPERSEDES STANDARD PLAN B15-5 DATED MAY 1, 2006 - PAGE 295 OF THE STANDARD PLANS BOOK DATED MAY 2006.

6

C47240

CIVIL


Exp. 12-31-07



BARRIER SECTIONS

Ö

ŏ



#4 NOTES I THROUGH Ⅵ:

#4

#4

(b) bars

@ 1'-4" Max @ 1'-4" Max

Maximum (a) bars

#4

#4

#5

#6

н

I. Details shown are primarily to conform design of sound walls to Type 736S and Type 736 SV Concrete Barriers. For sound wall details conforming with barriers see Standard Plan B15-7 and Revised Standard Plan RSP B15-8.

5'-0"

7'-0"

9'-0"

Compressive

Strength

of CMU

(psi)

1900

1900

1900

1900

1900

3750

(psi)

1500

1500

1500

1500

1500

2500

Н

6'-4"

8'-4"

10'-4"

12'-4"

14'-4"

16'-4"

- II. For details and sections not shown, see Standard Plan B15-7 and Revised Standard Plan
- II. Slope ground at traffic side of barrier to drain. Maximum slope ±10%. See Std Plan B11-56, Note D.
- II. Pile spacing may be varied, but shall not exceed the tabular values. See Revised Standard Plan RSP B15-8.
- I. For Case 1 ground line to be at the same elevation on both sides of the barrier. Barrier shall not be used to retain earth.
- Ⅲ. See Standard Plan B15-9 for other details.


- A. For type of block, type of block bond, and joint finish, see other sheets.
- B. When blocks are laid in stacked bond, Media Diocks die Idia in Slacke Dolla, indicate in State Dolla, indicate in State Dolla, indicate in Shall be provided. A minimum of 2-9 gauge wires continuous at 4-0" maximum to be used, Locate reinforcement in Joints that are at the approximate midpoint between bond beams.
- C. Horizontal joints shall be tooled concave or may be weathered. Vertical joints shall be tooled concave or may be raked.
- D. For intermediate wall heights (H), or barrier depths (H $_{\rm e}$), that are between the values given, use the tabular information for the next higher (H) or (H $_{\rm e}$).
- E. Class 2 concrete to be used for the barrier.
- F. Masonry strengths are listed in the "SOUND WALL REINFORCEMENT TABLE".


STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

SOUND WALL MASONRY BLOCK ON TYPE 736S/SV BARRIER DETAILS (1)

NO SCALE

RSP B15-6 DATED OCTOBER 5, 2007 SUPERSEDES STANDARD PLAN B15-6 DATED MAY 1, 2006 - PAGE 296 OF THE STANDARD PLANS BOOK DATED MAY 2006.





* @ 2" at option of Contractor.

.98

| | CASE 1: PILE DATA TABLE | | | | | | | | | |
|--------------|-------------------------|--------|---------------|--------|--------|---------------|----------|-------|---------------|--------------|
| Ø = 25 Min | | | Ø | | | | ø = 35 i | Min | | |
| Maximum H | s | L | Pile Reinf | S | L | Pile Reinf | S | L | Pile Reinf | Maximum H |
| 6'-4" | 10'-0" | 8'-6" | #6 Tol 6 | 10'-0" | 7'-0" | #6 Tol 6 | 10'-0" | 6'-0" | #6 Tol 6 | 6'-4" |
| 8'-4" | 10'-0" | 9'-6" | #6 Tol 6 | 10'-0" | 8'-0" | #6 Tol 6 | 10'-0" | 7'-0" | #6 Tol 6 | 8'-4" |
| 10'-4" | 10'-0" | 10'-6" | #6 Tol 6 | 10'-0" | 9'-0" | #6 Tol 6 | 10'-0" | 7′-6" | #6 Tol 6 | 10'-4" |
| 12'-4" | 10'-0" | 11'-6" | #7 Tol 6 | 10'-0" | 9'-6" | #7 Tol 6 | 10'-0" | 8'-6" | #6 Tol 6 | 12'-4" |
| 14'-4" | 10'-0" | 12'-6" | #7 Tol 7 | 10'-0" | 10'-6" | #7 Tol 7 | 10'-0" | 9'-0" | #7 Tol 7 | 14'-4" |
| 16'-4" | 10'-0" | 13'-0" | #8 Tol 7 | 10'-0" | 11'-6" | #8 Tol 7 | 10'-0" | 9'-6" | #7 Tol 7 | 16'-4" |

| | CASE 2: PILE DATA TABLE | | | | | | | |
|----------------|-------------------------|--------|------------|---------------|--------|--------|---------------|--------------|
| | | | ø = 30 Min | | | = 35 M | in | |
| Н _е | Maximum H | s | L | Pile Reinf | s | L | Pile Reinf | Maximum H |
| | 6'-4" | 10'-0" | 15'-0" | #7 Tol 6 | 10'-0" | 12'-0" | #6 Tol 6 | 6'-4" |
| | 8'-4" | 9'-9" | 16'-0' | #7 Tol 6 | 10'-0" | 13'-0" | #7 Tol 6 | 8'-4" |
| 1'-0" | 10'-4" | 8'-0" | 16'-0" | #7 Tol 6 | 10'-0" | 14'-0" | #7 Tol 6 | 10'-4" |
| 1 -0 | 12'-4" | 6'-9" | 16'-0" | #7 Tol 6 | 10'-0" | 15'-0" | #8 Tol 7 | 12'-4" |
| | 14'-4" | 5'-9" | 16'-0" | #7 Tol 6 | 9'-6" | 15'-6' | #8 Tol 7 | 14'-4" |
| | 16'-4" | 5'-0" | 16'-0" | #7 Tol 6 | 8'-9" | 16'-0" | #8 Tol 7 | 16'-4" |
| | 6'-4" | 8'-3" | 16'-0" | #7 Tol 6 | 10'-0" | 13'-6" | #7 Tol 6 | 6'-4" |
| | 8'-4" | 7′-0" | 16'-0" | #7 Tol 6 | 10'-0" | 14'-6" | #7 Tol 7 | 8'-4" |
| 0/ 011 | 10'-4" | 6'-0" | 16'-0" | #7 Tol 6 | 10'-0" | 15'-3' | #8 Tol 7 | 10'-4" |
| 2'-0" | 12'-4" | 5'-3" | 16'-0" | #7 Tol 6 | 9'-9" | 16'-0" | #8 Tol 7 | 12'-4" |
| | 14'-4" | 4'-6" | 16'-0" | #7 Tol 6 | 8'-4" | 16'-0" | #8 Tol 7 | 14'-4" |
| | 16'-4" | 4'-0" | 16'-0" | #7 Tol 6 | 7'-4" | 16'-0" | #8 Tol 7 | 16'-4" |
| | 6'-4" | 6'-0" | 16'-0" | #7 Tol 6 | 10'-0" | 15'-3" | #8 Tol 7 | 6'-4" |
| | 8'-4" | 5'-3" | 16'-0" | #7 Tol 6 | 10'-0" | 16'-0" | #8 Tol 7 | 8'-4" |
| 3'-0" | 10'-4" | 4'-6" | 16'-0" | #7 Tol 6 | 8'-10" | 16'-0" | #8 Tol 7 | 10'-4" |
| 3 -0 | 12'-4" | 4'-0" | 16'-0" | #7 Tol 6 | 7′-10" | 16'-0" | #8 Tol 7 | 12'-4" |
| | 14'-4" | 3'-6' | 16'-0" | #7 Tol 6 | 6'-10" | 16'-0" | #8 Tol 7 | 14'-4" |
| | 16'-4" | 3'-3" | 16'-0" | #7 Tol 6 | 6'-2" | 16'-0" | #8 Tol 7 | 16'-4" |
| | 6'-4" | 4'-3" | 16'-0" | #7 Tol 6 | 8'-0" | 15'-6" | #8 Tol 7 | 6'-4" |
| | 8'-4" | 3′-10" | 16'-0" | #7 Tol 6 | 7'-4" | 15′-9" | #8 Tol 7 | 8'-4" |
| 4'-0" | 10'-4" | 3'-6" | 16'-0" | #7 Tol 6 | 6'-10" | 16'-0" | #8 Tol 7 | 10'-4" |
| 4 -0 | 12'-4" | 3'-2" | 16'-0" | #7 Tol 6 | 6'-3" | 16'-0" | #8 Tol 7 | 12'-4" |
| | 14'-4" | 3'-0" | 16'-3" | #7 Tol 6 | 5′-8" | 16'-0" | #8 Tol 7 | 14'-4" |
| | 16'-4" | 2'-10" | 16'-6" | #7 Tol 6 | 5'-0" | 16'-0" | #8 Tol 7 | 16'-4" |

DIST COUNTY ROUTE POST MILES SHEET TOTAL TOTAL PROJECT NO. SHEET N

To accompany plans dated .

NOTES:

- 1. For details not shown, see Revised Standard Plan RSP B15-6 and Standard Plan B15-7.
- 2. Lapped splices in spiral reinforcement shall be lapped at least 80 wire diameters. Spiral reinforcement at splices and at ends shall be terminated with a 135° hook with a 6" tail hooked around a longitudinal bar.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

SOUND WALL MASONRY BLOCK ON TYPE 736S/SV BARRIER DETAILS (3)

NO SCALE

RSP B15-8 DATED OCTOBER 5, 2007 SUPERSEDES STANDARD PLAN B15-8
DATED MAY 1, 2006 - PAGE 298 OF THE STANDARD PLANS BOOK DATED MAY 2006.

2006 RE VISE D STANDARD PLAN RSP ES -1A

ELECTROLIERS High mast light pole STANDARD TYPES Double Arm lighting standard 15, 15D ()---Existing electrolier 15 STRUCTURE 21, 21D STRUCTURE Electrolier foundation (Future installation) 30 NOTES: 1. Luminaires shall be 310 W HPS when installed on Type 21, 210, 30, 31, 32, 35 and 36-20A Standards, unless otherwise specified. Luminaires shall be 200 W HPS when installed on other type standards or poles, unless otherwise specified. 31 32 35 2. Luminaires shall be the cutoff type, ANSI Type Ⅲ medium cutoff lighting distribution, unless otherwise specified. 36-20A 3. Variations noted adjacent to symbol on project plans. Electrolier (see project notes or project plans) ✓ Luminaire on wood pole STANDARD NOTES: AB Abandon. If applied to conduit, remove conductors. BC Install pull box in existing conduit run. BP Pedestrian barricade, type as indicated on plan. CB Install conduit into existing pull box. Connect new and existing conduit. Remove existing conductors and install conductors as indicated. Conduit to remain for future use. Remove conductors. Install pull wire or rope. Detector handhole. FΑ Foundation to be abandoned. IS Install sign on signal mast arm. NS No slip base on standard. PEC Photoelectric control. PEU Photoelectric unit. RC Equipment or material to be removed and become the property of the Contractor. RE Remove electrolier, fuses and ballast. Tape ends of conductors. RL Relocate equipment. Remove and reuse equipment. RS Remove and salvage equipment. SC Splice new to existing conductors. SD Service disconnect. Standard to remain for future use. Remove luminaire, pole conductors, fuses and ballast. TSP Telephone service point.

00

ABBREVIATIONS AND EQUIPMENT DESIGNATIONS PROPOSED EXISTING

| BBS | bbs | Dottery bookup avotem |
|------------|-----------|--|
| BC | bc | Battery backup system Bolt circle |
| C | C | Conduit |
| ссту | cctv | Closed circuit television |
| CKT | ckt | Circuit |
| CMS | cms | Changeable message sign |
| DLC | dlc | Loop detector lead-in cable |
| EMS | ems | Extinguishable message sign |
| EVC | evc | Emergency vehicle cable |
| EVD | evd | Emergency vehicle detector |
| FB | fb | Flashing beacon |
| FBCA | fbca | Flashing beacon control assembly |
| FBS | fbs | Flashing beacon with slip base |
| FO | fo | Fiber optic |
| G | G | Ground (Equipment Grounding Conductor) |
| GFCI | GFCI | Ground fault circuit interrupt |
| HAR | har | Highway advisory radio |
| HEX | hex | Hexagonal |
| HPS | hps | High pressure sodium |
| IISNS | iisns | Internally illuminated street name sign |
| ISL | isl | Induction sign lighting |
| LED | led | Light emitting diode |
| LMA | Ima | Luminaire mast arm |
| LPS | lps | Low pressure sodium |
| LTG | I+g | Lighting |
| LUM MAT | lum | Luminaire |
| MAI | mat | Mast arm mounting vehicle signal faces, |
| MAS | mas | top attachment Mast arm mounting vehicle signal faces, |
| MAS | ilius | side attachment |
| MAS-4A | mas-4A | Mast arm mounting vehicle signal faces, |
| MAS-4B | mas-4B | side attachment - 4 signal section |
| MAS-4C | mas-4C | arde diridenilleni 4 argilar section |
| MAS-5A | mas-5A | Mast arm mounting vehicle signal faces, |
| MAS-5B | mas-5B | side attachment - 5 signal section |
| MC | mc mc | Mercury contactor |
| M/M | m/m | Multiple to multiple transformer |
| MT | m† | Conduit with pull wire or rope only |
| MTG | m†g | Mounting |
| | m√ | Mercury vapor lighting fixture |
| N | N | Neutral (Grounded Conductor) |
| NC | NC | Normally closed |
| NO | NO | Normally open |
| PB | pb | Pull box |
| PEC | pec | Photoelectric control (Type I, I, II, II or |
| | | ∑as shown) |
| PED | ped | Pedestrian |
| PEU | peu | Photoelectric unit |
| PPB RL | ppb | Pedestrian push button |
| RM RM | | Relocated equipment |
| SB | rm | Ramp metering |
| SIC | sb sic | Slip base |
| SIG | siq | Signal interconnect cable Signal |
| SMA | sma | Signal mast arm |
| SNS | sns | Street name sign |
| SP | sp | Service point |
| TDC | †dc | Telephone demarcation cabinet |
| TMS | tms | Traffic monitoring station |
| TOS | tos | Traffic Operations System |
| VEH | veh | Vehicle |
| XFMR | xfmr | Transformer |
| COMM | comm | Communication |
| RWIS | rwis | Roadway weather information system |
| | | |

| DIST | COUNTY | ROUTE | TOTAL P | | SHEET NO. | SHEET |
|--------|--------------|---|--------------|----------------|-----------------------------|--------|
| | | | | | | |
| | Huy B | L WH | ENGINEER | PROF | ESS ION | |
| | tober 5 | | | Jeffer NoE1 | y G. McRo 4512 -30-08 | _) â (|
| agents | shall not be | rnia or its offi responsible for electronic copie | the accuracy | N. ELE | | / *// |

To accompany plans dated _

SOFFIT AND WALL MOUNTED LUMINAIRES

Pendant, 70 W HPS unless otherwise specified.

unless otherwise specified.

Wall surface, 70 W HPS unless otherwise specified.

→ Existing soffit or wall luminaire to remain unmodified.

NOTE:

Arrow indicates "street side" of luminaire.


STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

ELECTRICAL SYSTEMS (SYMBOLS AND ABBREVIATIONS)

RSP ES-1A DATED OCTOBER 5, 2007 SUPERSEDES STANDARD PLAN ES-1A DATED MAY 1, 2006 - PAGE 400 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-1A





401

REVISED STANDARD PLAN RSP ES-1B

ROUTE POST MILES SHEET TOTAL TOTAL PROJECT NO. SHEETS

Jeffery G. McRoe
No. E14512
Exp. 6-30-08
ELECTRICAL

| EQUIPMENT IDENTIFICATION ILLUMINATED SIGN IDENTIFICATION NUMBER: Sign No. 12345 Transformer rating (kVA) Lighting control type Number and type of fixtures ELECTROLIER OR EQUIPMENT IDENTIFICATION NUMBER: 12345 - 15'-0" Mast arm length, if shown. Do not place on standard or structure. Equipment number - Place on standard or structure. Existing equipment numbers are shown in parenthesis | | External conductor Conductor or bus Tie point Contactor, Contact NO Terminal blocks Contactor, Contact NC Enclosure bond Grounding electrode Circuit breaker Receptacle | 5 J | VEHICLE Vehic 9 U U = 1 L = 1 Slot Input | ower number in input file file (I or J) |
|--|--|--|------------|--|--|
| $(1/2"C_3/\sqrt{2#10, 15#14, 2 DLC})$ Number and size of conductors and cables | 3 9A(21) Pull box-Add | | PROPOSED | EXISTING | |
| Size of conduit in inches Ø1, Ø2, Ø2P, etc. Traffic phase identification for signal faces, detectors and phase diagrams | descriptions | tional designations or unications pull box | <u> </u> | | Type A detector loop. Outline of sawcut shown. |
| 1 2 3 Project note numbers (A) (B) (C) Equipment description, installation or item numbers (A) | 6 = No. 6 pull box (S) = Sprin 7 = No. 7 (Ceiling pull box) (21) = Anch 8 = No. 8 (Pendant soffit pull box) 9 = No. 9 pull box (T) = Traf | | \Diamond | | Type B detector loop. Outline of sawcut shown. |
| SIGNAL AND LIGHTING STANDARD (TYPICAL DESIGNATION): 19A - 37 - 100 Wind velocity = 100 mph | 9A = No. 9A pull box | | | 1888 | Type C detector loop. Outline of sawcut shown. |
| Case 3 arm loading Standard type Standard Plan sheet number Detail number or letter | | | | 7771 | Type D detector loop. Outline of sawcut shown. |
| | | | | | Type E detector loop. Outline of sawcut shown. |
| MISCELLANEOUS EQUIPMENT PROPOSED EXISTING | | | | 1777 1441 1441 | Type Q detector loop. Outline of sawcut shown. |
| CMS Changeable message sign ([]]{ Closed circuit television camera | | | • | <==] | Magnetic detector |
| Highway advisory radio pole and antenna | | | ● | dh | Detector handhole |
| Extinguishable message sign | | | | 17.7.7.7.7.7.7.7.7.7.7.7.7.7.7.7.7.7.7. | Microwave or video detection zon |
| V V = Video image sensor | | | | DEPART | TATE OF CALIFORNIA MENT OF TRANSPORTATION ICAL SYSTEMS |

402

AL SYSTEMS (SYMBOLS AND ABBREVIATIONS)


NO SCALE

RSP ES-1C DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-1C DATED MAY 1, 2006 - PAGE 402 OF THE STANDARD PLANS BOOK DATED MAY 2006.


REVISED STANDARD PLAN RSP ES-1C



To accompany plans dated ____



TYPE II-A SERVICE EQUIPMENT ENCLOSURE



Ö

 Δ

TYPE II-B SERVICE EQUIPMENT ENCLOSURE

NOTES-TYPE I SERVICE EQUIPMENT ENCLOSURES:

- Service equipment enclosures and metering equipment shall meet the requirements of the service utility.
- Service equipment enclosures shall be factory wired NEMA 3R construction and shall be provided with dead front panel and provisions for padlocking.
- Control wiring shall be 600 V, No. 14 AWG stranded (THHN) machine tool wire. Where subject to flexing, 19 strand wire shall be used.
- 4. Main bus shall be rated for 125 A and shall be tin-plated copper.
- An engraved phenolic nameplate on the dead front panel indicating the function of each circuit or device shall be installed with stainless steel rivets or stainless steel screws.
 - a) Adjacent to the breaker or device with character size a minimum of $\frac{1}{8}$.
 - b) At the top of the exterior door panel indicating system number, voltage level and number of phases with character size a minimum of %.
- 6. A plastic laminated wiring diagram shall be provided and attached to the inside of the front door.
- In unpaved areas, a raised portland cement concrete pad of 2'-0" x 4" x width
 of service equipment enclosure foundation or controller cabinet foundation
 shall be constructed in front of Type II service equipment enclosure.
- Internal bus, where shown, is typical only. Alternative designs of proposed service equipment enclosure shall be submitted to the Engineer for approval.
- 9. Circuit breakers may be mounted in the vertical or horizontal position.
- Dimensions of service equipment enclosures shall meet the requirements of the service utility.
- Minimum clearance shall be required for front and back of service equipment enclosures per National Electrical Code, Article 110.26, "Spaces About Electrical Equipment (600 Volts, Nominal, or Less)."

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

ELECTRICAL SYSTEMS (SERVICE EQUIPMENT TYPE II SERIES)

NO SCALE

RSP ES-2B DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-2B DATED MAY 1, 2006 - PAGE 404 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-2B

NOTES-TYPE II SERVICE EQUIPMENT ENCLOSURES:

- Service equipment enclosure and metering equipment shall meet the requirements of the service utility. The meter area shall have a sealable, lockable, weathertight cover that can be removed without the use of thous.
- Service equipment enclosures shall be factory wired and conform to NEMA standards.
- Dimensions of service equipment enclosures shall meet the requirements of the service utility.
- 4. The dead front panels on Type II service equipment enclosures shall have a continuous stainless steel or aluminum piano hinge. The panel in front of the breakers shall be secured with a latch or captive screws. No live parts shall be mounted on the dead front panel.
- 5. The exterior door shall have provisions for padlocking. The padlock hole shall be a minimum diameter of $\frac{1}{16}$ ".
- 6. Enclosures housing transformers of more than one kVA shall have effective screened ventilation louver of not less than 50 square inches. Screen shall be stainless steel No. 304, with a No. 10 size mesh. Framed screen shall be secured with at least four bolts.
- Fasteners on the exterior of the enclosure shall be vandal-resistant and shall not be removable from the exterior. Exterior screws, nuts, bolts and washers shall be stainless steel.
- 8. Landing lugs for incoming service conductors shall be compatible with either copper or aluminum conductors sized to suit the conductors shown on the plan. Landing lugs shall be copper or tin-plated aluminum. Neutral bus shall be rated for 125 A and be suitable for copper or aluminum conductors unless otherwise specified. The terminal shall include but not be limited to:
 - a) Incoming terminals (landing lugs)
 - b) Neutral luas

05

- c) Solid neutral terminal strip
- At least 6 standard single pole circuit breaker spaces, ¾" nominal, shall be provided for branch circuits. Circuit breaker interiors shall be copper. Interiors of enclosure shall accept plug-in or cable-in/cable-out circuit breakers.
- Control wiring shall be 600 V, 14 stranded machine tool wire. Where subject to flexing, 19 strand wire shall be used.
- 11. Main bus shall be rated for 125 A and shall be tin-plated copper.
- 12. A plastic laminated wiring diagram shall be provided with brass mounting eyelets and attached to the inside of the enclosure and the wiring diagram shall be affixed to the interior with a UL or ETL approved method.

- 13. An engraved phenolic nameplate on the dead front panel indicating the function of each circuit or device shall be installed with stainless steel rivets or stainless steel screws:
 - a) Adjacent to the breaker or device with character size a minimum of V_8 ".
 - b) At the top of the exterior door panel indicating State system number, voltage level and number of phases with character size a minimum of $\frac{1}{3}c^{-1}$
- 14. The plan shows the approximate location of devices within the enclosure. Components may be rearranged, however, the "working" clearances within the service equipment enclosure shall be maintained.
- 15. In unpaved areas a raised portland cement concrete pad 2'-0" x 4" x width of foundation shall be constructed in front of new service equipment enclosure installation. Pad shall be set to elevation of foundation.
- 16. Foundation shall extend 2" minimum beyond edge of service equipment enclosure.
- Internal bus, where shown, is typical only. Alternative design of proposed service equipment enclosure shall be submitted to the Engineer for approval.
- Plug-in circuit breakers may be mounted in the vertical or horizontal position. Cable-in/cable-out circuit breakers shall be mounted in the vertical position.
- Type II-AF and Type II-BF service equipment enclosures shall have the meter viewing windows located on the front side of the service equipment enclosures.
- 20. Type II-AR and Type II-BR service equipment enclosures shall be similarly constructed as Type II-AF and Type II-BF respectively, except the meter viewing windows shall be located on the back side of the service equipment enclosures.
- 21. Minimum clearance shall be required for front and back of service equipment enclosure per National Electrical Code, Article 110.26, "Spaces About Electric Equipment (600 Volts, Nominal, or Less)."

OCTOBER 5 DESCRIPTION OF THE STATE STATE OF THE STATE OF

To accompany plans dated _____

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION


ELECTRICAL SYSTEMS (SERVICE EQUIPMENT NOTES TYPE III SERIES)

NO SCALE


RSP ES-2C DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-2C DATED MAY 1, 2006 - PAGE 405 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-2C

; -2G



7.10




Load

area

condui+

| TYP | E III-B SERVICE (120/2 | 40 V) EQUIPMENT LEGEND | | | | |
|---|-----------------------------|-------------------------------|--|--|--|--|
| ITEM No. | COMPONENT | NAME PLATE DESCRIPTION | | | | |
| ① | Neutral lug | | | | | |
| ② ③ | Landing lug (Note 6) | | | | | |
| 3 | Test bypass facility | | | | | |
| 4) | Meter socket and support | | | | | |
| (5) | Terminal blocks | | | | | |
| 6 | Neutral bus | | | | | |
| 7 | Ground bus | | | | | |
| 8 | Grounding electrode | | | | | |
| 9 | 30 A, 2PNO Contactor | Sign Illumination | | | | |
| 0 | Photoelectric unit (Note 7) | | | | | |
| Ũ | 15 A, 1P, Test switch | Sign Illumination Test Switch | | | | |
| 13 | 15 A, 120 V, 1P, CB | Sign Illumination Control | | | | |
| (3) | 15 A, 120 V, 1P, CB | Flashing Beacon | | | | |
| (4) | 30 A, 240 V, 2P, CB | Sign Illumination | | | | |
| ٩ | 100 A, 240 V, 2P, CB | Main Breaker | | | | |
| (T) | 30 A, 240 V, 2P, CB | Lighting | | | | |
| (| 50 A, 120 V, 1P, CB | Signals | | | | |
| 8 | 30 A, 120 V, 1P, CB | Ramp Metering | | | | |
| (19) | 20 A, 120 V, 1P, CB | Irrigation | | | | |
| 8 | 15 A, 120 V, 1P, CB | Lighting Control | | | | |
| \(\text{Q} \tag{\text{Q}} \text | Photoelectric unit (Note 7) | | | | | |
| 2 | 15 A, 1P, Test switch | Lighting Test Switch | | | | |
| 3 | 60 A, 2PNO Contactor | Lighting | | | | |
| 3 | 15 A, 120 V, 1P, CB | IISNS | | | | |
| 23 | 30 A, 2PNO Contactor | IISNS | | | | |
| 29 | 20 A, 120 V, IP, CB | Telephone Demarcation Cabinet | | | | |

107



TYPE III-B SERVICE EQUIPMENT **ENCLOSURE FOUNDATION DETAILS**

SIDE VIEW

FRONT VIEW

NOTES: (FOR SERVICE EQUIPMENT ENCLOSURE) Voltage ratings of service equipment shall conform to the service voltages indicated on the plans.

2. Unless otherwise indicated on the plans, service equipment items shall be provided for each service equipment enclosure as shown.

Connect to remote test switch mounted on lighting standards, sign post or structure when required.

4. Items No. (1) and (6) shall be isolated from the service equipment enclosure.

5. Meter sockets shall be 5 clip type.

6. The landing lug shall be suitable for multiple conductors.

7. Type I photoelectric control shall be used unless otherwise indicated on the plans.


STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

ELECTRICAL SYSTEMS (SERVICE EQUIPMENT AND TYPICAL WIRING DIAGRAM. TYPE III-B SERIES)

NO SCALE

RSP ES-2E DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-2E DATED MAY 1, 2006 - PAGE 407 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-2E



0.17

NOTES: (FOR SERVICE EQUIPMENT ENCLOSURE) 3. Connect to remote test switch mounted on lighting standards, sign post or structure when required. Voltage ratings of service equipment shall conform to the service voltages indicated

(2

Auto

120 V Flashing beacons

Reading cover

36" thick polycarbonate

ultraviolet-resistant

120 V Irrigation — — 120 V TDC — #

TYPE III-DF SERVICE EQUIPMENT ENCLOSURE

WITH PROVISIONS FOR ONE 100 A METER (TYPICAL)

(12)

(15)

(19) (26)

on the plans.

480 V Sign

Ó

ŏ

illumination J

(9)

2. Unless otherwise indicated on the plans, service equipment items shall be provided

Three-phase, 277/480 V, 4-wire by the service utility

for each service equipment enclosure

Note 3 ===

- - -

- 4. Items No. 1) and 6) shall be isolated from the service equipment enclosure.
- Meter sockets shall be the 7 clip type.
- The landing lug shall be suitable for multiple conductors.
- 7. Type I photoelectric control shall be used unless otherwise indicated on the plans.
- 8. Service pedestal shall meet the requirements of EUSERC 308 or 309 in addition to the information given on this sheet.

=<u>=</u>={Note 3

Note 13

Note 11

Note 12

-Note 10

lighting

--- 120 V IISNS

(23)

(5) (22

⊣ ⊦ -

Main bonding jumper

GB

- N (120 V Neutral conductor)

240 V Intersection Lighting


enclosure

Ground bus secured to service equipmen-

- 9. Color of insulation of the neutral shall be gray for the 277/480 V system and shall be white for the 120/240 V system.
- 10. 120/240 V transformer grounded circuit conductor (neutral conductor).
- 11. 120/240 V transformer grounding electrode conductor.
- 12. 120/240 V system neutral bus and ground bus.


Service conduit


13. 120/240 V enclosure bonding jumper.



To accompany plans dated.

TYPE III-D SERVICE (277/480 V) EQUIPMENT LEGEND





120 V Signals

31(24)(17)

277/480 V SERVICE WIRING DIAGRAM (TYPICAL)

120 V Ramp metering

51

╚╏┉╏

RSP ES-2G DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-2G DATED MAY 1, 2006 - PAGE 409 OF THE STANDARD PLANS BOOK DATED MAY 2006.

STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

ELECTRICAL SYSTEMS

(SERVICE EQUIPMENT AND


TYPICAL WIRING DIAGRAM.


TYPE III-D SERIES)

NO SCALE

REVISED STANDARD PLAN RSP ES-2G

TYPE III-D SERVICE EQUIPMENT **ENCLOSURE FOUNDATION DETAILS**





 Δ



Thermostatically controlled switch,

To accompany plans dated.

NON-GFCI

NON-GFCI

WIRING DIAGRAM

NOTES:

- 1. Telephone demarcation cabinet shall be furnished with a mounting panel, outlets, circuit breaker and deadfront plates in place. Dimensions are nominal.
- An approved mastic or caulking compound shall be placed on the foundation prior to placing the cabinet to seal openings between the bottom of the cabinet and the foundation.
- In unpaved areas, a raised PCC pad shall be placed in front of the telephone demarcation cabinet. Pad shall be 2'-0" x 1'-10" x 4" thick, with 2" above the finished grade.
- 4. All conduits shall be bonded to the enclosure.
- 5. Telephone demarcation cabinet:
 - a) Material shall be anodized aluminum ($\frac{1}{8}$ " thick).
 - b) Fabrication shall conform to the requirements of the Standard Specifications.
 - c) The exterior door shall be side hung and secured with a padlockable draw latch, the padlock hole shall be a minimum diameter of 1/16" to receive a padlock.
 - d) Ventilation louvers shall be located on the door.
 - e) Fan shall be mounted in a ventilator housing.
 - f) Fan shall be thermostatically controlled and adjustable to turn on between 80°F and 130°F .
 - g) Fan circuit shall be fused at 175 percent of the fan motor capacity.
 - h) Fan capacity shall be at least 25 cubic feet per minute.
 - i) Fasten fixed mounting panels with nuts, lock and flat washers to % 0 x 1" studs welded to enclosure.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION


ELECTRICAL SYSTEMS (TELEPHONE DEMARCATION CABINET, TYPE B)

NO SCALE

RSP ES-3E DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-3E DATED MAY 1, 2006 - PAGE 414 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-3E





ES

-5A

POST MILES SHEET TOTA TOTAL PROJECT NO. SHEET

Jeffery G. McRo

eo. E14512

Exp. 6-30-08

ELECTRICAL

Lifting 1. M. Pal HEGINTERED ELECTRICAL ENGINEER

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this pi

To accompany plans dated.

October 5, 2007


PLANS APPROVAL DATE

LOOP INSTALLATION PROCEDURE

- 1. Loops shall be centered in lanes.
- 2. Saw slots in pavement for loop conductors as shown in details.
- Distance between side of loop and a lead-in saw cut from adjacent detectors shall be 2'-0" minimum. Distance between lead-in saw cuts shall be 6" minimum
- 4. Bottom of saw slot shall be smooth with no sharp edges.
- Slots shall be washed until clean, blown out and thoroughly dried before installing loop conductors.
- Adjacent loops on the same sensor unit channel shall be wound in opposite directions.
- Identify and tag loop circuit pairs in the pull box with loop number, start (S) and finish (F) of conductor. Identify and tag lead-in-cable with sensor number and phase.
- 8. Install loop conductor in slot using a $\frac{1}{6}$ " to $\frac{1}{4}$ " thick wood paddle. Hold loop conductors with wood paddles (at the bottom of the sawed slot) during sealant placement.
- 9. No more than 2 twisted pairs shall be installed in one sawed slot.
- Allow additional 5'-0" of slack length of conductor for the lead-in run to pull box.
- 11. The additional length of each conductor for each loop shall be twisted together into a pair (6 turns per 3'-4" minimum) before being placed in the slot and conduit leading to pull box.
- 12. Test each loop circuit for continuity, circuit resistance and insulation resistance at the pull box before filling slots.
- 13. Fill slots as shown in details.

23

- 14. Splice loop conductors to lead-in-cable. Splices shall be soldered.
- 15. End of lead-in-cable and Type 2 loop conductor shall be waterproofed prior to installing in conduit to prevent moisture from entering the cable.
- 16. Lead-in-cable shall not be spliced between the pull box and the controller cabinet terminals.
- 17. Test each loop circuit for continuity, circuit resistance and insulation resistance at the controller cabinet location.
- 18. Where loop conductors are not to be spliced to a lead-in-cable, the ends of the conductors shall be taped and waterproofed with electrical insulating coating.




TYPE 1A TYPE 2A TYPE 3A TYPE 4A INSTALLATION INSTALLATION INSTALLATION


SAWCUT DETAILS


(Type A loop detector configurations illustrated)


1. 1A thru 4A = 1 Type A loop configuration in each lane.
2. 1B thru 4B = 1 Type B loop configuration in each lane.
3. 1C = 1 Type C loop configuration each lane.
4. 1D thru 4D = 1 Type D loop configuration in each lane.
5. 1E thru 4E = 1 Type B loop configuration in each lane.
6. 10 thru 4C = 1 Type O loop configuration in each lane.
(Use Type A, B, C, D, E or O loop detector configurations only when specified or shown on plans)











2 1 1 3 2 1 1 Splice

See Notes 6 and 7

4 3 2 1

TYPICAL LOOP CONNECTIONS
(Dashed lines represent the pull box)

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

ELECTRICAL SYSTEMS (DETECTORS)

NO SCALE

RSP ES-5A DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-5A DATED MAY 1, 2006 - PAGE 423 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-5A


SECTION A-A


SECTION B-B

SECTION C-C


SLOT DETAILS - TYPE 1 AND TYPE 2 LOOP CONDUCTOR

POST MILES SHEET TOTAL TOTAL PROJECT NO. SHEET





ELEVATION
TYPE 15 AND TYPE 21 BARRIER RAIL MOUNTED



States Popos REGISTERED CIVIL ENGINEER


1/4

-Bar 1/4" x 5"

DETAIL R
LUMINAIRE ARM CONNECTION

23/8" Ø hole. Chased edges for electrical

conductors



BASE PLATE

| | LUMINAIRE ARM DATA | | | | | | | | | |
|--|--------------------------|-----------|----------------------|----------------------|---------|---------|--|--|--|--|
| | M Projected Length | N Rise | Min OD At Pole | Nominal Thickness | P | | | | | |
| | | | | | Type 15 | Type 21 | | | | |
| | 6'-0" | 2'-0"± | 31/4" | 0.1196" | 31'-6"± | 36'-6"± | | | | |
| | 8'-0" | 2'-6"± | 31/2" | 0.1196" | 32'-0"± | 37′-0"± | | | | |
| | 10'-0" | 3'-3"± | 3%" | 0.1196" | 32'-9"± | 37′-9"± | | | | |
| | 12'-0" | 4'-3"± | 3%" | 0.1196" | 33'-9"± | 38'-9"± | | | | |
| | 15'-0" | 4'-9"± | 41/4" | 0.1196" | 34'-3"± | 39'-3"± | | | | |

| | POLE | Α | Min OD | | Wall | | D1 Bolt | Thick- | Anchor Bolts | LUMINAIRE ARM | |
|---|------|--------|--------|--------|-----------|-------|---------|--------|----------------------|------------------|--|
| | TYPE | Height | Base | Тор | Thickness | ٠ | Circle | ness | Size | AI.M | |
| [| 15 | 30′ | 8" | 3 7/8" | 0.1196" | 1'-0" | 1'-0" | 1" | 1" Ø x 3'-0" x 4"* | 6' - 15' 12' | |
| | 21 | 35′ | 8%" | 3%" | 0.1196" | 1'-0" | 1'-0" | 1" | 11/4"ø × 3'-0" × 4"* | 6' - 15' 12' | |
| | | | | | | | | | | | |

* For barrier rail bolts, see Standard Plan ES-6B.

BASE PLATE DATA

NOTES:

1. Indicates arm length to be used unless otherwise noted on the plans.

POLE DATA

- 2. For Type 15-SB, use Type 15 standard with Type 30 slip base plate details, see Standard Plan ES-6F.
- 3. For additional notes, see Standard Plan ES-7M and ES-7N.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION


ELECTRICAL SYSTEMS (LIGHTING STANDARD TYPES 15 AND 21)

NO SCALE

RSP ES-6A DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-6A DATED MAY 1, 2006 - PAGE 427 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-6A







DATED MAY 1, 2006 - PAGE 438 OF THE STANDARD PLANS BOOK DATED MAY 2006.


REVISED STANDARD PLAN RSP ES-7B














7 10 07









154




DETAIL A
CONDUIT TERMINATION

SECTION A-A





SIDE VIEW
DETAIL I
CONDUIT TERMINATION



DETAIL C
CONDUIT TERMINATION

October 5, 2007
PLANS APPROVAL DATE
The State of Cultivation for the ordinary of the country of

POST MILES SHEET TOTAL TOTAL PROJECT NO. SHEET

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION


ELECTRICAL SYSTEMS (ELECTRICAL DETAILS STRUCTURE INSTALLATIONS)

IN SCALE


RSP ES-9A DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-9A DATED MAY 1, 2006 - PAGE 454 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-9A














99



FRAMING DETAILS





CROSS-SECTION OF SIGN

Note

See Wiring Notes and Symbols on Revised Standard Plan RSP ES-14B.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION


ELECTRICAL SYSTEMS (LED EXTINGUISHABLE MESSAGE SIGN 10" LETTERS)

NO SCALE

RSP ES-14A DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-14A DATED MAY 1, 2006 - PAGE 466 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-14A

To accompany plans dated __



167

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION


ELECTRICAL SYSTEMS (LED EXTINGUISHABLE MESSAGE SIGN WIRING DIAGRAM)

NO SCALE

RSP ES-14B DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-14B DATED MAY 1, 2006 - PAGE 467 OF THE STANDARD PLANS BOOK DATED MAY 2006.

REVISED STANDARD PLAN RSP ES-14B







NOTES: (FOR LIGHTING AND SIGN ILLUMINATION CONTROL)

- The ballast voltages of lighting fixtures and luminaires shall match line service voltages.
- 2. Voltage rating of photoelectric controls shall conform to the service voltage indicated on the plans.
- 3. Terminal strip shall be provided for wiring to fixtures.
- 4. Type SC1A, SC2A, SC3A controls are similar to Types SC1, SC2 and SC3 controls respectively except test switch and wiring are not required.





Photoelectric unit



TYPE LC1 CONTROL

For 120 V unswitched circuit with no more than 800 W load.

N


TYPE LC2 CONTROL

For 120 V unswitched circuit

TYPE LC3 CONTROL

-15 A test switch

For 240 V and 480 V unswitched circuits




TYPE SC1 CONTROL

For 240 V or 480 V switched circuit, see Note 4 for Type SC1A

TYPE SC2 CONTROL

For 120 V switched circuit, see Note 4 for Type SC2A



NO SCALE

RSP ES-15D DATED OCTOBER 5, 2007 SUPERCEDES STANDARD PLAN ES-15D DATED MAY 1, 2006 - PAGE 472 OF THE STANDARD PLANS BOOK DATED MAY 2006.